The Regional Municipality of Niagara

2019-T-105 (Contract RN 19-05)

Reconstruction of Regional Road 98 (Montrose Road) From Regional Road 49 (McLeod Road) to Charnwood Avenue in the City of Niagara Falls

Addendum No. 3

I Directive

This addendum shall form an integral part of the plans and specifications for the above project and shall be read in conjunction therewith. This addendum shall, however, take precedence over all requirements of the previously issued drawings and specifications with which it may prove to be at variance, unless otherwise clarified by the Engineer.

This addendum must be signed by the Tenderer in the appropriate space and must be attached to the back of the Form of Tender and placed in the Envelope for submission at the time of tendering. **Tenders not including this addendum signed as requested shall be rejected as informal.**

II Information

The below bidders attended the Mandatory Site Visit;

1. **Alfidome Constructions Niagara**
2. **Alfred Beam Excavating Limited**
3. **Beam-Rankin Join Venture Limited**
4. **Brennan Paving Ltd.**
5. **Demar Construction Inc.**
6. **Norjohn Contracting and Paving Limited**
7. **O'Hara Trucking and Excavating**
8. **Peter's Excavating Inc.**
9. **Rankin Construction Inc.**
10. **GAMS**

III Revisions

1. Special Provisions - Supplementary Special Provisions

SSP8 CONSTRUCTION SIGNS, TRAFFIC CONTROL & TRAFFIC MANAGEMENT PLAN

ADD the following:

A road closure will be allowed for the duration of all work related to the installation of municipal services (i.e. watermain, sanitary sewer, and storm sewer) between Sta. 0+280 (MacBain Centre north entrance) and Sta. 0+700 (Kinsmen Court). Niagara Region will be responsible for the supplying, installing, maintaining, and removing advance warning signs and associated detour signs for the duration of the closure.

The Contractor will be responsible for supplying, installing, maintaining, and removing the necessary road closure signs and barriers at the limits of the road closure.

The Contractor will be responsible for maintaining pedestrian access, compliant with AODA requirements, through the road closure zone for the duration of the closure. In addition, the Contractor will be responsible for notifying, and coordinating with, all emergency services, municipal waste collection, and transit companies (including school transit).

IV Questions and Answers

Question 1:
Section 6 (Electrical) has several items indicating that the contractor is to supply yet in section 7, these same items are being supplied by the Region. Please provide confirmation that the contractor is to supply:

- 6.02 – Junction boxes
- 6.05 – Sectional steel poles
- 6.06 – Streetlight arm, luminaire and photocell
- 6.08 – Anchor assembly for concrete pole base

Answer 1:
Section 6 in the Schedule of Tender Prices relates to the supply and installation of street lighting. The contractor is responsible for the supply of all materials under Section 6. Section 7 relates to the supply and installation of traffic signals. The contractor is responsible for the supply of all materials under Section 7 unless indicated otherwise that an item will be supplied by Niagara Region.

End of Addendum No. 3
No. of Pages: 2

Date Issued: April 1, 2019

Signature: Vicki Lafford-Field
Purchasing Agent

The Tenderer Shall Adjust Their Bid Price According To The Changes Specified in this Addendum.

Name of Company: _____

Tenderer's Signature _____

Date: _____